(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPY, Bhoppi, M.P.)

Gold Kit Mandir, Gwallor (M.P.) - 474,005, INDIA (2) | 1 | 2 |

Envil / MKT / Consultancy / No. | Gold Kit Mandir, Gwallor (M.P.) - 474,005, INDIA (2) | 1 | 2 |

Ph.: +91-751-2409300, Hax +91751-2604684, e-mail: director@mitsgwallol.hr; Hebsite: www.rightsgwallor.hr

Estd. 1957

Principal,

TESTING CONSULTANCY REPORT

Kendriya Vidyalaya No.3.,

Morar Cantt.,

Gwalior (MP) - 474006

MITS Dispatch

Ref.: No. F/1106/1-2/KV-3/Gwl/Technical Audit/410 dated 16.08.21

Sub.: Structural safety audit of K.V. 03 Building, Morar Cantt., Gwalior

Sir,

Kindly find enclosed herewith the inspection report for above said work.

Note:

Received Rs. 81703/- against consultancy charges vide cheque No. 194588 dated 13.08.2021

Dr. Jayvant Choudhary Asst. Prof., CED

Dr. Abhilash Shukla Asst. Prof. CED

Dr. M.K. Trivedi

Prof. & Head CED

Forwarded:

This Testing/Consultancy report is forwarded on the recommendations of the Department responsibility of Test/Consultancy Report lies with the concerning department.

Rs. 81703/ Challan No. TRM. CO-AA 9 60057 Date: 13,8-21

1 20

MITS, GWALLOR FESTING / CONSULTANCY REPORT MITS, GWALLOR TESTING / CONSULTANCY

11:31 Accounts Officer

Book No.: MITS TCR/XXIV

DIRECTOR 1.11.21



JOR TESTING / CONSULTANCY REPORT MITS, GWALIOR TESTING / CONSULTANCY REPORT

MITS, GWALIOR TESTING / CONSULTANCY REPORT

MITS, GWALIOR TESTING / CONS

MADHAY INSTITUTE OF TECHNOLOGY & SCIENCE, GWALIOR

(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in

TESTING / CONSULTANCY REPORT MITS Dispatch

Detailed Structural Audit Report of Kendriya Vidyalaya No.3

With reference to the letter No.F.1106/1-2/KV-3/Gwl/Technical Audit/410 dated on 16 August, 2021, committee visited Kendriya Vidyalaya No.03 situated at Morar Cantt., Gwalior to carry out the structural audit of the structure. Details of the Structural audit are collected in the Performa. Structure is G + 1 and the type of structure is reinforced concrete framed structure. Committee has physically verified the structure and rebound hammer testing was done at least 10% of the total columns, beams & slabs available in the structure. On the basis of the observations, following is recommended.

• Dampness and spalling of concrete are observed in boy's toilet & girl's toilet of ground floor near to chemistry laboratory. It is recommended to provide adequate water proofing at the terrace. It is also observed that reinforced is visible and is corroded Following steps are recommended:

For inspection, it is necessary to expose the corroded locations up to such an extent that these locations can be seen through naked eye. First step in treatment of rusting on reinforcement is cleaning of rust with the wire brush. After cleaning, tamp the surface with hammer having the weight at least 5 lbs. Then rub the surface with wire brush or hessian rope. In the market, many rust removing chemicals are also available. Those chemicals can be used if cleaning of rust is to be done more effectively. In important members (members that has to carry heavy load) of RC structures, sand blasting can be used for cleaning of rust. If the cleaned surface is found heavily corroded, then the surface can be coated with black ship paint (that paint is marine paint). This paint usually seals off the steel surface and prevents the further corrosion. Corroded members which are critical in the whole structure such as columns should be additionally reinforced by using hooked or anchorage connections or by using beams, corroded slabs can be additionally reinforced by using wire mesh (which is locally said to be as Jali).

• It is observed that drinking water facility near to chamistry laboratory needs to be repaired and proper water fittings to replace so that the drinking water facility can be made available to students.

GWALIOR TESTING / CONSULTANCY REPORT MITS, GWALIOR TESTING / CONSULTANCY REPORT MITS, GWALIOR TESTING / CONSULTANCY REPORT

Book No.: MITS TCR/XXIV



(A Govt. Aided DGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.) - 474 005, INDIA

Ph.: +31.751.WMMI for +31.751.W44444 c could director floriting matter by croticities www.mitagwallor.in

TESTING / CONSULTANCY REPORT MITS Dispatch

- Mild cracks have been observed in room no.7 near wi..dow and diagonal crack is observed in
 the wall of the same room. It is recommended to provide proper concrete cover and plaster
 repairing of the existing cracks.
- Large crack has been observed in the wall of room no. 10. It is recommended for proper filling and sealing of crack should be performed.
- Diagonal crack has been observed on inside and outside wall of the conference hall, room no.
 4, room no. 27, due to seismic activity in the near past. So, proper filling and scaling of the crack has to be performed.
- Settlement of outer columns at the backside of the school structure has been observed.
 Footing remediation has to be performed by concrete underpinning, jet grouting, micro piles or by using expanding geopolymers.
- Horizontal cracks on the wall of biology laboratory have been observed. It is recommended to seal and fill the crack properly.
- Construction joints have been exposed and clearly visible at room no. 16, room no. 13, room
 no. 20, adjacent to music room. It is important to fill and cover the joints properly till the
 terrace so that dampness can be prevented.
- Cracks in the beam have been observed in room no. 16. It is important to assess the depth of
 the crack and proper retrofitting action required to be performed as it is a horizontal member.
- Reinforcement has been exposed in boy's toilet in ground floor. Dampness and spalling of
 concrete has also been observed. So, retrofitting action as recommended in the first point has
 to be performed.
- Joint between the wall and the plinth beam has been observed in room no.23. It is
 recommended to assess the depth of the cracks and seci the joints effectively.
- Cracks in column in front of toilet in the ground floor have been observed. It is important to replacement and seal the crack cover concrete in the columns.
- Local settlement in the central area has been observed due to which cracking at the joints at
 ground floor, first floor and parapet wall has been observed. It is important to provide
 remediation in the settled area as mentioned in the above bullet point no. 6.
- Dampness in the staircase area moving to first floor, girls toilet near to room T-8, room no.
 29, room no. 34, room no. 33, room no. 34, room no. 35, room no. 43, room no. 44, room no.

Book No.: MITS TCR/ XXIV

MITS OWNLOR TESTING CONSULTANCE REPORT. WITS GIVEL OR TESTING CONSULTANCE REPORT. WITS CHARLES FOR SUMMER AND STREET

ITE OF TECHNOLOGY & SCIENCE, GWALIOR

(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in

TESTING / CONSULTANCY REPORT

45, room no. 51, room no. 53, room no. 54 & room no. 57. Water proofing has to be properly performed at the terrace level to stop the seepage and dampness in the rooms not only at first floor but at ground floor also.

- Spalling of concrete due to corrosion of reinforcement has been observed in ladies toilet near to T-11. So, similar retrofitting action has to be performed as mentioned above.
- Construction joint has to be sealed and properly covered near to room no. 39& room no. 46.
- Minor cracks in beam and wall has been observed in room no. 40. Proper filling and sealing of cracks has to be performed.
- Large cracks in the tie beam and wall has been observed in room no. 47. Proper filling and sealing of cracks has to be performed.
- Inner and outer wall cracks have been observed near to room no. 45. Similarly, outer wall cracks have been observed in room no. 46. Proper filling and sealing of cracks has to be
- Cracks at the bottom face of the slab in the gallery near to boy's toilet (T-9). Proper filling and sealing of cracks has to be performed.
- Damp proof course has been provided in 2015. It has been observed that in the damp proof course the joints are not properly sealed. As a result, dampness and seepage in seen in the first and ground floor level. It is recommended to seal the joints of the terrace slab and then provide adequate damp proof course with proper sealing of joints.
- Improper drainage has been observed at the terrace. It is recommended to provide adequate drainage with properly maintaining the slopes towards the drains. Also, it has been seen that existing drainage openings are either small or clogged. It is recommended to properly unclog
- Cracks in the plaster have been observed at the base of water tank. It is recommended to remove the cracked plaster and replace it with new plaster with epoxy coating.
- Reinforcement of the roof slab of parking lot is corroded and concrete is continuously spalling. It is recommended to remove the cracked concrete and along with the retrofitting action of corroded concrete new rebars to be attached and welded for better serviceability and durability of the structure.

Book No.: MITS TCR/XXIV



(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwaiior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwallor.in, website: www.mitsgwallor.in

TESTING / CONSULTANCY REPORT

Following is the structure audit details in the proforma:

MITS Dispatch

STRUCTURAL AUDIT REPORT

Name of the Building: Kendriya Vidyalaya No.03

Description: School building.

Address: Morar Cantt., Gwalior (M.P)

Age of the Building: 27 years (Constructed on 1994).

Inspection Report Date: // INSPECTED BY: 04 October, 2021

MITS, GWALLOR TESTING / CONSULTANCY REPORT MITS, GWALLOR TESTING / CONSULTANCY REPORT MITS, GWALLOR TESTING / CONSULTANCY REPORT

OBSERVATIONS

CN	Description	Locations	Remarks
S.No	Description Spalling of concrete and	Ceiling of car parking	Exposed reinforcement
1	exposure of reinforcement	55g	and rusting
	Exposed reinforcement	In boys toilet of ground	Exposed reinforcement
2	Exposed felliforcement	floor	and rusting
3	Cracking	Room No. 7	Mild cracks near
3	Cracking		window and diagonal
			crack at the wall
4	Cracking	Room No. 10	Large crack at the wall.
5	Cracking	Conference hall	Diagonal crack on
6	Cracking	Room No. 4	inside and outside wall
7.	Cracking	Room No. 27	
8.	Cracking	Biology lab	Horizontal cracks
9.	Settlement	Backside of the	Settlement of outer
<i>j</i> .		building	columns
10.	Construction joints	Room no. 16, Room no.	Open and exposed
10.		13, Room no. 20,	construction joints
		Adjacent to music room	
11.	Open joints	Room No 23	Open joint between the
***	J		wall and the plinth
			beam
12.	Cracking	In front of toilet in the	Cracks in column
12.	C	ground floor	
13	Local settlement	Central area	Cracking at the joints
15	Doub Settioniont		in ground floor, first
			floor and parapet wall
			has been observed due
			to settlement.
14	Construction joint	Near Room No. 39 and	
17	Communication John	46	joint
15.	Cracking	Room No 40	Minor cracking
16	Cracking	Room No 47	Large cracks in the tie
10	Cracking	KUUIII INU 47	Large cracks in the ne

Book No.: MITS TCR/ XXIV

MITS, OWALIOR TESTING / COMSULTANCY REPORT - MITS, OWALIOR TESTING / CONSULTANCY REPORT - MITS, OWALIOR TESTING / CONSULTANCY REPORT

Sr. No.: 2020 094

Scanned with CamScanner



WILD CANVERSAL RESIDEN A COSHRENA INVESTMENDEL

MADHAY INSTITUTE OF TECHNOLOGY & SCIENCE, GWALIOR

(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Fh.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in

TESTING / CONSULTANCY REPORT MITS Dispatch

			beam and wall
17.	Cracking	Near boys toilet T9	Cracks at the bottom
18.	Tear in Damp proof course	Several spots at roof	Serious tear and break in the DPC on roof
19	(DPC) Improper drainage	Roof	Improper drainage and blockage of drain at
		Water tank on roof	roof Cracks in the plaster of
20	Cracking at water tank	Boys toilet	the beam support. Excessive dampness
21	Dampness	Girl's toilet near	Excessive dampness
22	Dampness and spalling of concrete	chemistry lab	

7. Inspection of structural component using rebound hammer

S.No	Description	Type of Member	Location Location	Augle of Test	Compressive Strength (MPa)
			Near Chemistry Lab	90°	19.0
1	Cl	Column	Near Boys Toilet of	90°	15.0
2	C2	Column	Ground Floor		
		0.1	Near Room 10	90°	16.5
3	C3	Column	Near Channel Gate	90°	17.0
4	C4	Column	of First Floor		
		C. Ivera	Near Room 44	90°	17.0
5	C5	Column	Near Room 16	90°	19.5
6	C6	Column	Near Room 31	90°	16.0
7	C7	Column	Near Channel Gate	90°	21.5
9	C8	Column	Near Room 42	90°	14.5
10	Bl	Beam	Near channel gate	90°	17.0
11	B2	Beam	(first floor)		
			Near Room 23	90°	15.0
12	B3	Beam		90°	16.0
13	B4	Beam	At Car Parking		15.0
14	B5	Beam	Near Boys Toilet of		
			First Floor	90°	14.0
15	B6	Beam	In Classroom 5A	90°	13.0
15	S1	Slab	In Room 34	90°	14.0
16	S2	Slab	At car parking		12.0
17	S3	Slab	At T8 Boys toilet	90°	
18	S4	Slab	At gallery first floor	90°	14.0
	S5	Slab	Near Channel Gate	90°	12.5
19	33		of First Floor		
20	56	Slab	At staircase	90°	14.5
20	S6	Siau	connecting ground		
			and first floor		

Book No.: MITS TCR/XXIV

WHEN DAMPING FRANCE SEASON

Sr. No.: 2020 0 9 5








Photo 5: Open joint between wall and plinth beam near
Room 23

Book No.: MITS TCR/XXIV

MITS Diapatch






Photo 6:Open joint at Ground Floer



(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.) - 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in

TESTING / CONSULTANCY REPORT MITS Dispatch



Photo 7:Big Wall Crack in Room 47





Photo 9: Open joint in Room 41



CORTESTING / CONSULTANCY REPORT MITS, GWALTOR TESTING / CONSULTANCY REPORT MITS, GWALTOR TESTING / CONSULTANCY

Book No.: MITS TCR/XXIV



Photo E: Cracking on the stage located at ground flo





Photo 10: Open joint adjoining Room 23



Sr. No.: 2020 0 97





(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.) - 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwallor.in, website: www.mitsgwallor.in

TESTING / CONSULTANCY REPORT MITS DISpatch

Photo 11: Excessive dampness in Room 34



Photo 13: Outer wall crack in Room 45




Photo 15: Crack on the outer wall adjoining the water tank and detrioration in the support of the water tank





Photo 17: Diagonal cracking on the classroom wall Book No.: MITS TCR/XXIV

MITS, GWALIOR TESTING / CONSULTANCY REPORT MITS, GWALIOR TESTING / CONSULTANCY REPORT MITS, GWALIOR TESTING / CONSULTANCY REPORT



Pheto 14: Dampness and cracking in Rcom 44



Photo 16: Diagonal crack on the outer wall



Photo 18:Open joint near Class 10th: Sr. No.: 2020 $\tilde{0}$ 98

S, OWALIOR TESTING / CONSULTANCY REPO

MADHAV INSTITUTE OF TECHNOLOGY & SCIENCE, GWALL (A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2664684, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in

TESTING / CONSULTANCY REPORT






Photo19 and 20: DPC is improperly attached to the roof flooring




Photo 21:Blockage/improper drainage in drains located



Photo 22: Cracking in outer wall adjoining chemis lab

Sr. No.: 2020 099

Book No.: MITS TCR/XXIV NG / CONSULTANCY REPORT - METS, GWALLOR TESTING / CONSULTANCY REPORT - MITS GWALLOR TESTING / CONSULTANCY REPORT - MITS GWALLOR TEST

(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, Fax: +91-751-2554584, e-mail: director@mitsgwallor.in, website: www.mitsgwallor.in

TESTING / CONSULTANCY REPORT MITS Dispatch




Photo 23: Break/tear in DPC on the roof




Photo 25: Dampness in the ceiling of Car Parking




Photo 24: Break/tear in DPC on the roof



Phase 26: Excessive concrete deterioration and reinfort ment exposure in the ceiling of car parki

Book No.: MITSTCR/XXIV



(A Govt. Aided UGC Autonomous & NAAC Accredited Institute Affiliated to RGPV, Bhopal, M.P.)

Gola ka Mandir, Gwalior (M.P.)- 474 005, INDIA

Ph.: +91-751-2409300, e-mail: director@mitsgwalior.in, website: www.mitsgwalior.in



Photo 27: Spalling of concrete in the roof slab of car parking



Photo 28: Spalling of concrete and exposure of reinforcement in the ceiling of car parking

8. Recommendations:

The condition of the structure is very poor which requires major renovation as suggested above. Age of structure is 27 years, it is recommended not to extend the structure as the non destructive testing indicates that the structure should not be extended further for its safety and structural stability.

Submitted for necessary action

(Member)

Dr. Jayvant Choudhary

(Member)

Professor & Head

Structure Audit Committee Structure Audit Committee Civil Engineering Department